



Kevin Keith, Director

**ADDENDUM 001
REQUEST FOR BIDS
Hampton Storage Building
Request for Bid 9-120810TV**

Bidders should acknowledge receipt of Addendum 001 (ONE) by **signing** and **including it** with the original bid. The due date for receipt of proposals remains **unchanged** by this Addendum. Accordingly, the following clarifications, questions and answers are believed to be of general interest to all potential Bidders. All other terms and conditions remain unchanged and in full force.

Name and Title of Signer (Print or type)	Name and Title of Department Authority Tom Veasman Senior General Services Specialist
Contractor/Offeror Signature	Department of Transportation
(Signature of person authorized to sign)	(Authorizing Signature)
Date Signed:	Date Signed: <i>(Insert date signed)</i>

On Page 2 of 18 on the Hampton Storage Building Drawings, an 8" PVC storm drain around 3 sides of the building runs into a 12" PVC pipe at the southeast corner of the building. The 12" PVC pipe should drain away from the building for 5 feet and be capped. No connection will be required at the end of the 12" PVC pipe.

The following note on Page 3 of 18 on the Hampton Storage Building Drawings has been rescinded: "Provide (1) 4" Sch 40 PVC with fiber optic sweep up through floor below the service panel 12" A.F.F. and cap, extend 24" below grade and 12" beyond the concrete apron and cap."

The following note should be added on Page 3: "A 6" PVC pipe sleeve shall be placed in the east concrete wall 1 foot from the south end of the building at a height of 2 feet from top of wall to top edge of the pipe. A 6" PVC pipe sleeve shall be placed in the middle wall 1 foot from the south side of the building at a height of 2 feet from top of wall to top edge of the pipe."

The following requirement on Page 9 of 18 on the Hampton Storage Building Drawings has been rescinded: "2 x 4 Bottom Chord Bracing Between Each Truss @ 24" O. C."

Vendor questions:

Question: We would like clarification on what door type is required: non-insulated or insulated or one of each?

Answer: Sheet 7 of 18 of the Hampton Drawings shows two 16' overhead doors (#1 and #4). Footnote A next to the DOOR SCHEDULE on Sheet 13 of 18 indicates door #1 is insulated and door #4 is not insulated.

Question: Are both doors motorized or just one door?

Answer: Sheet 18 of 18 shows that only door #1 is motorized. However, the work associated with the diagrams provided on Sheet 18 will be completed by others and is not part of this Request for Bid. Sheet 18 was provided for informational purposes only.

Note that contractors should bid this project with pricing for the products recommended in the Request for Bid. At MoDOT's discretion, comparable products may be accepted after the award is made if the products are determined to be of equal or greater quality.