



Kevin Keith, Director

**ADDENDUM 003
REQUEST FOR BIDS
Poplar Bluff RE Office Project
Request for Bid 9-121228TV**

Bidders should acknowledge receipt of Addendum 003 (THREE) by **signing** and **including it** with the original bid. The due date for receipt of bids is January 25th, 2013 @ 2:00 PM. Accordingly, the following clarifications, questions and answers are believed to be of general interest to all potential Bidders. All other terms and conditions remain unchanged and in full force.

Name and Title of Signer (Print or type)	Name and Title of Department Authority Name: Tom Veasman Title: Sr. General Services Specialist
Contractor/Offeror Signature	Department of Transportation 
(Signature of person authorized to sign)	(Authorizing Signature)
Date Signed:	Date Signed: 1-18-13

VENDOR QUESTIONS:

- 1) Alternate B includes the installation of salvaged cabinets in the storage and kitchenette areas to meet ADA Standards. What modifications will be required?

ANSWER: ADA requirements related to the kitchen cabinets are as follows:

- Drawing A4.0 – 5 Cabinet Detail indicates a height of 2' 10" to the top of the countertop/sink.
- Drawing A4.0 – 8 Break Room 120 indicates an "open knee space" under the sink.

- 2) More cabinet questions: What do we have? Where are they? Are we to transport to jobsite and or cabinet shop? Are the existing plastic laminate? Are they Oak? What kind of countertops do they have?

ANSWER: Plan revisions 5 – dated 1/10/2013, Sheet A4.0 – Detail 8; new base and wall cabinets and new countertops are specified.

Section 00100 Bidder Requirements – 1. Scope of Work – Alternate B:

1. Install New Cabinets in kitchenette area.
2. Fabricate and install laminate countertops in areas as indicated in plans.

- 3) Please clarify what type of insulation, backing, etc. is to be used on the exterior perimeter of the metal building.

ANSWER: 1) Exterior Wall Insulation - Equal to Simple Saver System, R-19 Double Layer Wall System. The outer layer to be placed between the wall sheets and girts, the inner layer to be installed between the girts. Provide full height .02 vapor barrier fabric between the girts and interior liner panels.

2) Roof Insulation - Equal to Simple Saver System, R-30 Double Layer System. The upper layer of fiberglass to be installed between the roof panels and the purlins, the lower layer to be installed between the purlins. The Simple Saver Suspension System to be all white with white grid system, fully encapsulating the purlins.